


— = Detour Route

Advance Warning Sign Spacing for Conventional Highways

Posted Speed (MPH)	Sign Spacing (Feet)	Taper Length 12' W (Feet)	Maximum Spacing of Devices	
			On a Taper	On a Tangent
30	120	180	30	60
35	160	245	35	70
40	240	320	40	80
45	320	540	45	90
50	400	600	50	100
55	500	660	55	110

THIS PLAN IS FOR ILLUSTRATIVE PURPOSES ONLY AND IS NOT INTENDED TO RELIEVE THE CONTRACTOR FROM THE REQUIREMENTS OF THE CONTRACT DOCUMENTS, THE MOST CURRENT VERSION OF THE TEXAS MUTCD AND ALL OTHER APPLICABLE REQUIREMENTS. ANY CHANGES TO THIS PLAN, WORK ZONE CONDITIONS, OR TRAFFIC CONDITIONS, ALSO DO NOT RELIEVE THE CONTRACTOR FROM MAINTAINING PROPER WORK ZONE SAFETY AND THE SAFETY OF THE GENERAL PUBLIC. ANY CHANGES SHALL MEET THE REQUIREMENTS OF THE CONTRACT DOCUMENTS, THE MOST CURRENT VERSION OF THE TEXAS MUTCD AND ALL OTHER APPLICABLE GUIDELINES AND SPECIFICATIONS.



City of Waxahachie	
Project Name N Oak Branch Rd - Road Closure	
Prime Contractor Enerpipe Ltd.	
Date 02/16/2018	Sheet Number Sheet 1
Engineer Axiom Management & Engineering, Inc. PO Box 6460 Fort Worth, Texas 76115 817-994-5420 Firm # F-3654	Drawn for Enerpipe Ltd. P.O. Box 2329 Amarillo, Texas 79105